

Passcert

Higher Quality, better service!



Q&A

[Http://www.passcert.com](http://www.passcert.com)

We offer free update service for one year.

Exam : D-PDD-DY-01

**Title : Dell PowerProtect Data
Domain Deploy v2 Exam**

Version : DEMO

1.An implementation engineer is racking a Dell PowerProtect Data Domain appliance at a customer site. The controller and all expansion shelves are in the rack, and all the data cables are connected.

What must they validate before connecting the power cables?

- A. The site supports three phase power to the rack
- B. The voltage aligns with the system requirements.
- C. There are dual power connections for the appliance
- D. There is a single power connection for the appliance

Answer: B

2.A security company requires limited access for their Dell PowerProtect Data Domain appliance. An account named DPAdmin is created with the limited-admin role. The user is able to log in to the Data Domain System Manager, but receives an Access Denied error when trying to open an FTP session.

What is the cause of this error?

- A. Only accounts with the admin role are permitted to access the system using FTP
- B. Only the sysadmin account is permitted to access the system using FTP
- C. Only accounts with the backup operator role are permitted to access the system using FTP
- D. Only accounts with the user role are permitted to access the system using FTP

Answer: A

3.A customer uses a backup application to backup data to a Dell PowerProtect Data Domain appliance. In their environment, they require:

- ☞ Dedicated SAN traffic
- ☞ No backup traffic on production IP network

Which connectivity option should the implementation engineer configure?

- A. Enable NFS
- B. DD Boost over FC
- C. Enable CIFS
- D. VTL over Ethernet

Answer: B

4.An implementation engineer finds that the Dell PowerProtect Data Manager fails to add the Dell PowerProtect Data Domain appliance. The connection test fails.

What three actions should be taken to resolve the issue? (Choose three.)

- A. Check DD Boost service status
- B. Verify network connectivity
- C. Upgrade the Data Domain to the latest versions
- D. Reboot the Data Domain appliance
- E. Check credentials.

Answer: ABE

5.Refer to the exhibit.

Enclosure Show Topology detailed

```
-----  
Port          enc.ctrl.port          enc.ctrl.port  
-----  
2a            > 2.B.H: 2.B.E > 3.B.H: 3.B.E  
2b            > 4.B.H: 4.B.E > 5.B.H: 5.B.E  
2c            > 7.A.H: 7.A.E > 6.A.H: 6.A.E  
2d  
3a            > 3.A.H: 3.A.E > 2.A.H: 2.A.E  
3b            > 6.B.H: 6.B.E > 7.B.H: 7.B.E  
3c            > 5.A.E: 5.A.H > 4.A.E: 4.A.H  
3d            >  
6a            >  
6b  
6c  
6d            >  
-----
```

Which port is the cable misconfiguration identified in the command output?

- A. 3a
- B. 2c
- C. 3c
- D. 2a

Answer: C